ANNEXURE-A

(A) SCOPE OF SUPPLY:

Supply of Electrical Items for Bridge No – 16, Majhi Bridge Site, Gorakhpur – Valmiki Nagar Doubling Project

(a) 1.5mm Dia 2 core PVC insulated copper cable – 1350 Mtr.
(b) 2.5mm Dia 2 core PVC insulated copper cable – 500 Mtr.
(c) 35 mm 4 Core Aluminium Armoured Cable – 1500 Mtr.
(d) Flood Light 200W – 80 Pcs.

(B) TECHNICAL SPECIFICATION:

The materials shall conform to the respective OEM standards and applicable Indian Standards (IS), as specified below:

Sl. No.	Description / Technical Specification	Acceptable Makes / Brands
(a)	1.5mm, 2-Core PVC Insulated Copper Cable, conforming to IS:694.	RR Kabel / Finolex / Havells
(b)	2.5mm, 2-Core PVC Insulated Copper Cable, conforming to IS:694.	RR Kabel / Finolex / Havells
(c)	35mm, 4-Core Aluminium Armoured Cable.	RR Kabel / KEI / Finolex
(d)	200W LED Flood Light, conforming to IS:10322 (Part 5, Section 5).	Ganit / Oreva / Philips

Offers for equivalent products of other reputed brands, in addition to the makes specified above, may also be considered, provided such products fully comply with the prescribed technical specifications, applicable quality standards and functional requirements. The Bidder shall submit relevant technical literature / datasheets in support of the compliance of the offered products, wherever required by BBJ.

SOUVIK BHATTACHARYA
Digitally signed by SOUVIK BHATTACHARYA
Date: 2026.11.11 11:23:00 +05'30'