

दी ब्रेथवेट बर्न एंड जेसप कंस्ट्रक्शन कंपनी लिमिटेड
The Braithwaite Burn And Jessop Construction Company Limited
(भारत सरकार का एक उद्यम) / (A Government of India Enterprise)

NIT No. eNIT/CCTV/GS&OE/10-2026

Date: October 23, 2026

Annexure – A

CONFIGURATION AND MINIMUM COMPONENTS REQUIRED

The minimum components required for the CCTV Surveillance System are indicated below. The list may be modified, increased or suitably adjusted by BBJ during execution, based on actual site conditions and operational requirements, subject to the terms and conditions of the Contract.

Any such variation shall be dealt with in accordance with the applicable provisions of the Contract and shall not, by itself, entitle the Contractor to any additional payment unless duly approved by BBJ.

Sl. No.	Component / Item	Make	Qty
1	CCTV IP Dome Camera with PoE (5 MP or above) with below features: • 5 MP PS CMOS Image Sensor or above • 3840 × 2160 @15fps, 2688×1520, @25/30fps or above • H.265+, H.264+ Dual-stream encoding or above • Support smart illumination • Lens should be 6.0mm or above • Should have inbuilt auto/sunny/night/outdoor white balance. • Accessories of camera and mounting accessories. • Should have inbuilt live sound recording system.	Pelco / Panasonic / Honeywell / Bosch / Infinova / Sony / Matrix / CP Plus / Hikvision / Dahua / Sparsh	6 Nos.
2	NVR 16 Channel with 2 or above HDMI port, 4K support, 2 or above storage slot. 2 × 4 TB or above surveillance-grade HDD for recording and RAID configuration. Storage should specially be designed for surveillance with 4 or above bitrate.	NVR: CP Plus / Hikvision / Matrix / Seagate / WD HDD: WD Purple / Seagate SkyHawk / Toshiba S300	NVR: 1 No. HDD: 2 Nos.
3	PoE 8 Port or above switch with accessories	Pelco / Panasonic / Honeywell / Hikvision / Infinova / Matrix / CP Plus / D-Link / Cisco / Netgear	2 Nos.

दी ब्रेथवेट बर्न एंड जेसप कंस्ट्रक्शन कंपनी लिमिटेड
The Braithwaite Burn And Jessop Construction Company Limited
(भारत सरकार का एक उद्यम) / (A Government of India Enterprise)

NIT No. eNIT/CCTV/GS&OE/10-2026

Date: October 23, 2026

4	1 KVA UPS with Battery	APC / Luminous	1 No.
5	6 U or above Rack with accessories for installation of NVR and other peripherals.	VAL / D-Link / Nettrack / Reputed make	1 No.
6	20 Mtr. HDMI Cable with VGA Cable of suitable length (for installation of our existing TV)	Honeywell / Pelco / Panasonic / Bosch / Infinova / Sony / Matrix / CP Plus / Hikvision	1 No.
7	32-inch (80 cm) 4K UHD Smart Monitor , with display resolution of 3840 × 2160 pixels, complete with standard power cable, connectivity accessories and all items required for installation and operation.	Samsung M7 Vision AI Smart Monitor, Black	1 No.
8	UTP CAT 6 Cable (Unit - Mtr.)	AMP / D-Link / Molex / Finolex	As per actual measured and approved use.
9	1.5 sqmm 3 Core Power Cable (Unit - Mtr.)	Polycab	As per actual measured and approved use.
10	PVC Conduct with flexibles (Unit - Mtr.)	VAL / D-Link / Nettrack / Reputed make	As per actual measured and approved use.
11	RJ45 Jack (Unit - Pc)	AMP / D-Link / Molex / Finolex	As per actual measured and approved use.

दी ब्रेथवेट बर्न एंड जेसप कंस्ट्रक्शन कंपनी लिमिटेड
The Braithwaite Burn And Jessop Construction Company Limited
(भारत सरकार का एक उद्यम) / (A Government of India Enterprise)

NIT No. eNIT/CCTV/GS&OE/10-2026

Date: October 23, 2026

12	Complete I/O Box with accessories (Unit - Pc)	Reputed make	As per actual measured and approved use.
13	5 Mtr. CAT 6 patch cord (Unit - Pc)	AMP / D-Link / Molex / Finolex	As per actual measured and approved use.
14	2 Mtr. CAT 6 patch cord (Unit - Pc)	AMP / D-Link / Molex / Finolex	As per actual measured and approved use.
15	Cable laying with materials for laying, installation and configuration	Works	As per actual measured and approved use.

 Digitally signed by
SOUVIK BHATTACHARYA
Date: 2026.10.22 12:56:20
+05'30'